

Exhibit A
RMRA Project List for 2026/2027 Fiscal Year

Project Road	Project Location	Project Title	Project Type	Project Description	Pre-Construction Estimated Start	Pre-Construction Estimated Completion	Construction Estimated Start	Construction Estimated Completion	State Senate	State Assembly	Estimated Minimum Useful Life	Estimated Maximum Useful Life	Additional Project Elements
Bean Creek Rd	PM 1.05	BEAN CREEK RD PM 1.05	Other	This project will include: Slipout (60' L) - Recommend WB Shoulder Reconstruction, Drainage Improvements (New Storm Drain Through Wall) and Retaining Wall (Soldier Pile) Installation	01/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Bean Creek Rd	PM 1.87	BEAN CREEK PM 1.87	Other	Roadway Slipout, 50' long x 20' tall, Tree Fell due to unstable steep slope, A lot of groundwater near toe of failure, Soldier pile wall repair	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Bear Creek Rd	PM 2.39	BEAR CREEK RD PM 2.39	Other	24" cmp damaged and 20' of inlet crushed. Replace culvert and construct new headwalls	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Bear Creek Rd	PM 4.18	Bear Creek Rd PM 4.18	Other	Culvert Collapsed. Deformed from bottom. Approx. 4'. Jack and bore new culvert under roadway	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Bear Creek Rd	PM 6.73	Bear Creek Rd PM 6.73	Other	This project will include repair of a Road edge slipout 30' x 60"	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Bear Creek Rd	PM 7.41	Bear Creek Rd PM 7.41	Other	Road Edge slipped out 30' long. Recommend shoulder pile wall	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Browns Valley Rd	PM 2.93	Browns Valley Rd PM 2.93	Other	Slipout (10' L) - NB Shoulder Reconstruction, RSP and Drainage Improvements	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Cassery Rd	PM 2.93	Cassery Rd PM 2.93	Other	Slipout (20' W x 80' L) - EB/SB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-27	May-28	Sep-28	17	30	50 Years	75 Years	No
Cassery Rd	PM 3.39	Cassery Rd PM 3.39	Other	Slipout (20' W x 20' L) - EB/SB Shoulder Reconstruction and Drainage Improvements	02/2017	Jun-27	May-28	Sep-28	17	30	50 Years	75 Years	No
China Grade Rd	PM 0.62	CHINA GRADE PM 0.62	Other	Culvert failure washed out roadway. Temporary bridge placed until bottomless arch culvert can be placed	01/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Countywide	All Roads	Countywide Roadway Culvert Survey	Other	Countywide Roadway Culvert Survey	05/2020	07/2027	-	-	17	29	50	50	No
Countywide	All Roads	Countywide Roadside Vegetation Maintenance Project	Road Maintenance and Rehabilitation	Countywide Roadside Vegetation Maintenance Project	05/2020	07/2027	-	-	17	29	5	5	No
Countywide	All Roads	Countywide Roadside Drainage Maintenance Project	Road Maintenance and Rehabilitation	Countywide Roadside Drainage Maintenance Project	05/2020	07/2027	-	-	17	29	5	5	No
Countywide	All Roads	Countywide Culvert Maintenance Project	Road Maintenance and Rehabilitation	Countywide Culvert Maintenance Project	05/2020	07/2027	-	-	17	29	50	75	No
Countywide	All Roads	Countywide Roadbed Maintenance Project	Road Maintenance and Rehabilitation	Countywide Roadbed Maintenance Project	05/2020	07/2027	-	-	17	29	10	20	No
Countywide	All Roads	Countywide Striping Maintenance Project	Safety	Countywide Striping Maintenance Project	05/2020	07/2027	-	-	17	29	5	5	No
Countywide	All Roads	Countywide Signage Maintenance Project	Safety	Countywide Signage Maintenance Project	05/2020	07/2027	-	-	17	29	10	20	No
Countywide	All Roads	Countywide Guardrail Maintenance Project	Safety	Countywide Guardrail Maintenance Project	05/2020	07/2027	-	-	17	29	50	75	No
Countywide	All Roads	Countywide Pavement Planning/Grinding	Road Maintenance & Rehabilitation	This project will include: Pavement Rehab/Repair (Existing), Paving and/or Striping Rehab/Repair (Existing Safety)	05/2020	07/2027	-	-	17	29	50 Years	75 Years	No
Day Valley Rd	PM 1.18	Day Valley Rd PM 1.18 at Cox Rd	Other	This project will include repair of a Road edge slipout 25' x 10'	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
E Zayante Rd	PM 1.01	E Zayante Rd PM 1.01	Other	This project will include repair of a Road edge slipout	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
E. Cliff Dr	PM 2.25	E. Cliff Dr. PM 2.25 @ Schwan Lagoon	Other	This project will include repair of a Road edge slipout	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
E. Cliff Dr	17th Ave to Palisades Ave	E. Cliff Dr Pedestrian Improvements from 17th Ave to Palisades Ave	Other	Construct pedestrian and bike improvements	01/2023	12/2026	02/2027	01/2028	17	29	50 Years	75 Years	No
E. Cliff Dr	7th Ave to 14th Ave	E. Cliff Dr Pedestrian Improvements from 7th Ave to 14th Ave	Other	Construct pedestrian and bike improvements	01/2023	12/2026	02/2027	01/2028	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 0.35	EUREKA CANYON PM 0.35	Other	40 foot long slipout, 3 ft into road. Soldier pile repair	01/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 3.16	Eureka Canyon Rd PM 3.16	Other	Culvert Failure and Slipout (12' L) - SB (Outboard) Shoulder Reconstruction, Drainage Improvements including 36" Culvert Replacement and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 3.36	Eureka Canyon Rd PM 3.36	Other	Major Slipout (20+/-' W x 70' L) with Potential Deep Seated Landslide - NB Traveled Way and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 3.50	Eureka Canyon Rd PM 3.50	Other	Tree Fell on causing 25' long slipout on edge of roadway, RSP embankment repair	03/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 4.67	Eureka Canyon Rd PM 4.67	Other	Roadway/Embankment Settling (20' L) Caused by Fallen Trees and Near Existing Retaining Wall (Crib) - NB and SB Traveled Way and Shoulder Reconstruction, Drainage Improvements including RSP and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 5.05	Eureka Canyon Rd PM 5.05	Other	Slipout (25' L) - SB Shoulder Reconstruction, Drainage Improvements, RSP and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 5.33	Eureka Canyon Rd PM 5.33	Other	25' long slipout. Rock wall repair with roadway reconstruction	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 8.39	Eureka Canyon Rd PM 8.39	Other	Slipout (50' L) - SB Shoulder Reconstruction, Drainage Improvements, RSP and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Gaffey Rd	PM 0.03, 0.04	Gaffey Rd PM 0.03, 0.04	Other	Slipout (20' L) - EB (Outboard) Embankment Reconstruction, RSP and Drainage Improvements	02/2017	Jun-27	May-28	Sep-28	17	30	50 Years	75 Years	No
Gaffey Rd	PM 0.08	GAFFEY RD PM 0.08	Other	Damaged culvert to be replaced. Includes fish passage.	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No

Exhibit A
RMRA Project List for 2026/2027 Fiscal Year

Project Road	Project Location	Project Title	Project Type	Project Description	Pre-Construction Estimated Start	Pre-Construction Estimated Completion	Construction Estimated Start	Construction Estimated Completion	State Senate	State Assembly	Estimated Minimum Useful Life	Estimated Maximum Useful Life	Additional Project Elements
Geoffroy Dr	PM 0.03	Geoffroy PM 0.03	Other	This project will include: Shoulder Reconstruction, Drainage Improvements and possible Retaining Wall (Soldier Pile) Installation	01/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Glen Canyon Rd	PM 0.39	Glen Canyon Rd PM 0.39	Other	Sink Hole found near culvert inlet. Slipline or replace culvert	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Glenwood Cut-off	PM 0.02	Glenwood Cut-off PM 0.02	Other	Slipout (4' W x 35' L) - WB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Crib) Installation	02/2017	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Glenwood Dr	PM 2.02	Glenwood Dr PM 2.02	Other	Erosion Under Existing Retaining Wall (Soldier Pile) - Backfill of Eroded Slope, Drainage Improvements and Erosion Control	02/2017	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Granite Creek Rd	PM 0.47	Granite Creek Rd PM 0.47	Other	Slipout (50' L) - NB Shoulder Reconstruction, RSP and Overside Drain Replacement	02/2017	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Granite Creek Rd	PM 1.47	Granite Creek Rd PM 1.47 (@1409)	Other	This project will include repair of a Road edge slipout	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Green Valley Rd	PM 2.34	Green Valley Rd PM 2.34	Other	25' long x 15' deep slipout. Edge of road undermined 1-2 feet. Recommend shoulder pile wall	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 2.35	HAZEL DELL PM 2.35	Other	50' long slipout half way into roadway. Soil nail wall to stabilize and then MSE wall.	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 2.57	HAZEL DELL RD PM 2.57	Other	Slipout 50' long. Soldier pile repair with roadway reconstruction	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Hazel Dell Rd	2.69+	HAZEL DELL RD PM 2.69+	Other	This project will include: Shoulder Reconstruction, Drainage Improvements and possible Retaining Wall (Soldier Pile) Installation	01/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 3.43	Hazel Dell Rd PM 3.43	Other	This project will include repair of a Road edge slipout 6' x 6'	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Holohan Rd	Green Valley Rd to Hwy 152	Holohan Road Multi-Use Path	Other	Construct a multi-use path	06/2023	12/2026	02/2027	01/2028	17	30	50 Years	75 Years	No
Ice Cream Grade	PM 1.24	Ice Cream Grade Rd PM 1.24	Other	Road Edge failure above culvert wall above wingwall is failing. Construct new headwall	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Jamison Creek Rd	PM 1.61	Jamison Creek Road PM 1.61	Other	Slipout - 25' L x 10' D - Roadway and Shoulder Reconstruction and Installation of Soldier Pile Wall	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Jarvis Rd	PM 0.64	Jarvis Rd PM 0.64	Other	Slipout (6' W x 20+/-) - NB (Outboard) Traveled Way and Shoulder Reconstruction, Earth backfill and Downdrain	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Jarvis Rd	PM 0.68	Jarvis Rd PM 0.68	Other	Culvert Failure & Roadway/Embankment Settling - Roadway Reconstruction and Drainage Improvements including 18" Culvert and Headwalls SB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation.	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Jarvis Rd	PM 1.02, 1.04, 1.07	Jarvis Rd PM 1.02, 1.04, 1.07	Other	PM 1.02 - Slipout (20+/-' W x 60' L) - SB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation, PM 1.04 - Slipout (6' W x 40' L) - SB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Crib) installation	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Kings Creek Rd	PM 1.65	Kings Creek Rd PM 1.65	Other	Slipout and Damaged Downdrain - Installation of Gabion Baskets or RSP, Backfill and Reinstall Culvert	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Kings Creek Rd	PM 3.03	Kings Creek Rd PM 3.03	Other	Slipout (40' L) and Landslide - Roadway Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Kings Creek Rd	PM 3.16	Kings Creek Rd PM 3.16	Other	Slipout and Roadway/Embankment Settling - Roadway Reconstruction, Drainage Improvements, and Retaining Wall (Stitch Pile) Installation	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Little Basin Rd	PM 0.64	Little Basin Rd PM 0.64	Other	Slipout (35' L) - EB (Outboard) Roadway Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Little Basin Rd	PM 0.85	Little Basin Rd PM 0.85	Other	Slipout (80' L) - SB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Little Basin Rd	PM 1.50	Little Basin Rd PM 1.50	Other	30' long slipout along shoulder, recommend soldier pile wall	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Lockhart Gulch Rd	PM 0.35	LOCKHART GULCH PM 0.35	Other	60' long by 10' tall shoulder slipout. Cribwall repair recommended	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Lodge Rd	PM 1.07	Lodge Road PM 1.07	Other	60' longslipout. Only 5' left of road. Recommend shoulder pile or soil nail wall	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Lompico Rd	PM 0.70	Lompico Rd PM 0.70	Other	This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Lompico Rd	PM 0.80	Lompico Rd PM 0.80	Other	30' long slipout due to tree falling on shoulder of road. RSP repair	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Lompico Rd	PM 1.22	Lompico Rd PM 1.22	Other	Slipout (45' L) - NB Shoulder Reconstruction, Drainage Improvements, RSP and Retaining Wall (Crib) Installation	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Lompico Rd	PM 2.38	Lompico Rd PM 2.38	Other	Slipout (10' W x 25' L) - NB Travelled Way and Shoulder Reconstruction and Installation of Retaining Wall (Crib)	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Lompico Rd	West Dr	LOMPICO RD @ WEST DR	Other	This project will include: Landscape Safety Installation (New)	01/2023	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No

Exhibit A
RMRA Project List for 2026/2027 Fiscal Year

Project Road	Project Location	Project Title	Project Type	Project Description	Pre-Construction Estimated Start	Pre-Construction Estimated Completion	Construction Estimated Start	Construction Estimated Completion	State Senate	State Assembly	Estimated Minimum Useful Life	Estimated Maximum Useful Life	Additional Project Elements
Miller Cut-off Rd	PM 0.47	Miller Cut-off Rd PM 0.47	Other	Repair combined with Miller Cutoff 0.49. Slipout (15' W x 85'L) Adjacent to Existing Crib Wall (Installed 2016) - NB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Miller Cut-off Rd	PM 0.49	Miller Cut-off Rd PM 0.49	Other	Slipout (15' W x 85'L) Adjacent to Existing Crib Wall (Installed 2016) - NB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Morrell Rd	PM 0.85	Morrell Rd PM 0.85	Other	This project will include repair of a Road edge slipout	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Mt Bache Rd	PM 0.11	Mount Bache Rd PM 0.11	Other	This project will include repair of a Road edge slipout	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Mt Charlie Rd	PM 1.63	Mt Charlie Road PM 1.63	Other	100' roadway slipout with road closure. Recommend soldier pile wall with road reconstruction	02/2024	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Mt Charlie Rd	PM 1.66	Mt Charlie Road PM 1.66	Other	100' roadway slipout with road closure. Recommend soldier pile wall with road reconstruction	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Mt Charlie Rd	PM 1.94	Mt Charlie Road PM 1.94	Other	50' long slipout near culvert. Soldier pile wall repair	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Mt Charlie Rd	PM 4.48	Mt Charlie Road PM 4.48	Other	This project will include repair of a Road edge slipout 40' long	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Mountain View Rd	PM 0.25	Mountain View Rd PM 0.25	Other	This project will include repair of lost road shoulder	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Nelson Rd	PM 0.44	Nelson Rd PM 0.44	Other	Road washout due to clogged culvert/flooding. Place new culvert, place headwalls, and reconstruct roadway	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
North Rodeo Gulch Rd	PM 1.88	North Rodeo Gulch Rd PM 1.88	Other	This project will include repair of a road edge following tree fall and uprooting	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Mountain View Rd	PM 2.70	North Rodeo Gulch Rd PM 2.70	Other	This project will include repair of 3 sections of road edge damage: 15x4, 33x4, 2x2 feet	03/2024	05/2027	06/2027	12/2027	17	29	50 Years	75 Years	No
North Rodeo Gulch	PM 3.77	North Rodeo Gulch Road PM 3.77	Other	50' long slipout into roadway. Lane closed. Soldier pile wall repair	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
North Rodeo Gulch	PM 3.82	North Rodeo Gulch PM 3.82	Other	Slipout (6' W x 50' L) - SB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Old Santa Cruz Hwy	PM 1.01	Old Santa Cruz Hwy PM 1.01	Other	Slipout (50'L) - NB/EB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Old Santa Cruz Hwy	PM 1.06	Old Santa Cruz Hwy PM 1.06	Other	Slipout - NB/EB Traveled Way and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Old Santa Cruz Hwy	PM 1.20	Old Santa Cruz Hwy PM 1.20	Other	This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing) Slipout (10' W x 50' L) - Recommend NB/EB Traveled Way, Drainage Improvements and Shoulder Reconstruction and Retaining Wall (Crib) Installation	02/2017	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Old Santa Cruz Hwy	PM 1.36	Old Santa Cruz Hwy PM 1.36	Other	This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing) Slipout (12' W x 90' L) - Recommend NB/EB (Outboard) Traveled Way and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Paulsen Rd	PM 0.93	Paulsen Road Raising at PM 0.93	Other	This project involves raising approx. 1000 LF of roadway out of the floodplain to prevent seasonal road closures.	02/2024	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Porter Gulch Rd	PM 0.51	Porter Gulch Rd PM 0.51	Other	This project will include repair of a Road edge slipout	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Prescott Rd	PM 0.52	Prescott Rd PM 0.52	Other	Slipout - NB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Crib) Installation	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Redwood Dr	Oak Dr	REDWOOD DR @ OAK DR	Other	This project will include: Landscape Safety Installation (New) 40' long slipout on south side of culvert and failed section of cribwall undermining road on north side. Recommend rock slope protection backfill on one side and soil nail wall on other.	01/2023	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Redwood Dr	PM 0.19	REDWOOD DR PM 0.19	Other	This project will include: Landscape Safety Rehab/Repair (Existing), Pavement Improvement (New), Storm Drain/Culvert Installation (New) Culvert failure, undermining road. Recommend culvert replacement and adding headwalls	01/2023	Jun-26	May-27	Sep-27	17	29	50 Years	75 Years	No
Redwood Lodge Rd	PM 1.80	Redwood Lodge Rd PM 1.80	Other	Culvert Failure and temp repair failure. Must be replaced with a bridge. Embankment reconstruction, excavation and backfill, concrete headwall, 120" culvert, erosion control and revegetation.	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Redwood Lodge Rd	PM 2.02	Redwood Lodge Rd PM 2.02	Other	This project will include: Landscape Safety Rehab/Repair (Existing), Storm Drain and/or Culvert Rehab/Repair (Existing) Preparation of design and environmental documents for large Slipout (30' W x 120' L) and Landslide - Recommend Roadway Reconstruction and Retaining Wall (Stitch Pile) Installation	03/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Redwood Lodge Rd	PM 2.25	Redwood Lodge Rd PM 2.25	Other	Shoulder damage, 30' long, 2' into roadway. Recommend shoulder pile wall	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No

Exhibit A
RMRA Project List for 2026/2027 Fiscal Year

Project Road	Project Location	Project Title	Project Type	Project Description	Pre-Construction Estimated Start	Pre-Construction Estimated Completion	Construction Estimated Start	Construction Estimated Completion	State Senate	State Assembly	Estimated Minimum Useful Life	Estimated Maximum Useful Life	Additional Project Elements
Redwood Rd	PM 0.38, 0.40	Redwood Rd PM 0.38, 0.40	Other	PM 0.38 Slipout (50' L) - NB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation, PM 0.40 ULTRABLCK Retaining Wall Failure - NB (Outboard) Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile)	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Redwood Rd	PM 0.97	Redwood Rd PM 0.97	Other	10' long by 7' tall shoulder slipout encroaching a foot into roadway. Recommend shoulder pile wall	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Redwood Rd	PM 1.67	Redwood Road PM 1.67	Other	Damaged culvert and road shoulder from storms. Culvert replacement with headwalls	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Rider Rd	PM 0.77	Rider Rd PM 0.77	Other	This project will include repair of a Road edge slipout	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Rider Rd	PM 0.85	Rider Rd PM 0.85	Other	30' slipout along shoulder - RSP repair	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Rider Rd	PM 1.38	Rider Rd PM 1.38	Other	slipout along shoulder, recommend RSP repair	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Riva Ridge	PM 0.10	Riva Ridge Rd PM 0.10	Other	This project will include repair of a Road edge slipout	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
San Andreas Rd	PM 1.24	SAN ANDREAS RD PM 1.24	Other	This project will include: Landscape Safety Installation (New), Pavement Improvement (New), Storm Drain/Culvert Installation (New) Slipout (20' W x 40' L) - Recommend SB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
San Lorenzo Way	San Lorenzo River	San Lorenzo Way Bridge	Bridge Structure Repair/Rehab (Existing)	Replace Existing Bridge	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Schulties Rd	PM 0.40	Schulties Rd PM 0.40	Other	This project will include repair of a Road edge slipout 80'	01/2021	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Schulties Rd	PM 1.14	Schulties Rd PM 1.14	Other	This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design	2/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Smith Grade Rd	PM 0.52	Smith Grade PM 0.52	Other	This project will include repair of a Road edge slipout	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Smith Grade Rd	PM 4.06	Smith Grade Rd PM 4.06	Other	Slipout (25' W x 12' L) - EB (Outboard) Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Soquel Drive	Robertson St.	Soquel Drive Robertson St.	Traffic Control Devices	Install traffic signal, thermoplastic striping and curb ramps	02/2017	07/2026	08/2026	07/2027	17	29	50 Years	75 Years	No
Soquel Drive	Soquel Ave	Soquel Dr to Soquel Ave Dedicated Right Turn Lane	Other	Construct a dedicated right turn lane	01/2023	12/2026	02/2027	01/2028	17	29	50 Years	75 Years	No
Spanish Ranch Rd	PM 0.63	Spanish Ranch PM 0.63	Other	This project will include repair of a Road edge slipout	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Spreckles Dr	PM 0.04	SPRECKLES DR PM 0.04 @ SOQUEL DR	Other	This project will include: Shoulder Reconstruction, Drainage Improvements and possible Retaining Wall (Soldier Pile) Installation	01/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Stetson Rd	PM 0.18	Stetson Rd PM 0.18	Other	Cribwall and culvert failure completely closing roadway. Replace culvert and construct new cribwall and roadway reconstruction	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Summit Rd	PM 2.12	Summit Rd PM 2.12	Other	This project will include repair of a Road edge slipout	03/2024	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Swanton Rd	PM 0.72	Swanton Rd PM 0.72	Other	8' Concrete Arch Culvert Failure and Slipout (54' L) - Temporary Creek Diversion System, SB Travelled Way and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Swanton Rd	PM 3.00	Swanton Rd PM 3.00	Other	60' L slipout. Installing Soldier Pile Wall, Pavement and Shoulder Reconstruction	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Upper East Zayante Rd	PM 1.18	Upper East Zayante Rd PM 1.18	Other	Road edge slipped out from clogged bleeder, tree failure with shoulder damage. Recommend shoulder pile wall and roadway reconstruction	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Upper East Zayante Rd	PM 1.68	Upper East Zayante PM 1.68	Other	Slipout (45' L) Near Existing Retaining Wall (Crib) and Landslide - SB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Upper East Zayante Rd	PM 2.51	Upper East Zayante Rd PM 2.51	Other	30' long shoulder slipout. Recommend soldier pile repair	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No
Valencia Rd	PM 0.25	Valencia Rd PM 0.25	Other	Large slipout from above. Road damage about 50 long by 15' deep undermining edge of road and guardrails. Shoulder pile wall repair	02/2023	Jun-27	May-28	Sep-28	17	29	50 Years	75 Years	No